

令和7年度 林道前田伊藤線舗装工事 数量総括表

	計算式	数量	備考
幅員全体面積		688.14 m2	
控除 計	m	m2	
不陸整正		688.14 m2	
上層路盤工		688.14 m2	
AS舗装工		688.14 m2	
白実線	m + m =	m	
白破線	m / 2.00 =	m	
U字溝蓋	222.10 m / 0.61 =	364 枚	
舗装止コンクリート	m + 222.10 m =	222.10 m	CON=0.036 F=0.36
	CON 0.036 m2 * 222.10 m =	8.00 m3	
	F 0.36 m2 * 222.10 m =	79.96 m2	
舗装掘削全体	688.14 * 0.11 - 8.88 =	66.82 m3	舗装止掘削控除 8.88 m3
逸散	66.82 * 0.05 =	3 m3	
残土	66.82 * 0.95 =	63 m3	
舗装止掘削全体	222.10 * 0.16 =	35.54 m3	舗装掘削へ控除 222.10 * 0.04 = 8.88 m3
逸散	35.54 * 0.05 =	1.78 m3	
掘削	35.54 * 0.95 =	33.76 m3	
埋戻流用	222.10 * 0.080 =	17.77 m3	
逸散・流用	1.78 + 17.77 =	20 m3	
残土	33.76 - 17.77 =	16 m3	
逸散合計		23 m3	
残土合計		79.00 m3	
掘削合計		102.00	

数量控除	計算式	数量	備考
横断溝控除	1 m × m =	m2	
	2 m × m =	m2	
	3 m × m =	m2	
	4 m × m =	m2	
	5 m × m =	m2	
	6 m × m =	m2	
	7 m × m =	m2	
	8 m × m =	m2	
	9 m × m =	m2	
	10 m × m =	m2	
	11 m × m =	m2	
	12 m × m =	m2	
	13 m × m =	m2	
	14 m × m =	m2	
	15 m × m =	m2	
	16 m × m =	m2	
	17 m × m =	m2	
	18 m × m =	m2	
	19 m × m =	m2	
	20 m × m =	m2	
	21 m × m =	m2	
	22 m × m =	m2	
	23 m × m =	m2	
	24 m × m =	m2	
	25 m × m =	m2	
控除 計	m m	m2	

